



भारतीय पटसन निगम लिमिटेड  
The Jute Corporation of India Limited

(A Government of India Enterprise)

सी.आई.एन./ C.I.N.: U17232WB1971GOI027958

क्षेत्रीय कार्यालय: गौरीपुर / Regional Office: Gauripur

Super Market, Ward No1, Gauripur, Dhubri (Assam) – 783331



Ref No: JCI/GRP/RLD/NIQ/2024-2025/003

Date: 02-04-2024.

**URGENT: TENDER NOTICE (Through NIQ)**

- ☒ Sealed quotations are invited from Authentic, skilled, resourceful, and experienced parties for repairing boundary wall fencing of west end boundary of Gauripur JTM premises. The address of JTM is as follows:

The Jute Corporation of India Ltd.

Ward No 1, Supermarket.

PO & PS- Gauripur

District- Dhubri

PIN- 783331

Assam

- ☒ Scope of work:

(A) Installation of GI Chain link fencing in the west end boundary (from North-west corner to Gate No 2, approximately 150 feet) of JTM premises.

(B) Raw materials for installation of GI Chain link fencing in the West end boundary of JTM premises, must be provided by the party as per specifications mentioned below.

(C) Specifications of GI Chain link fencing as follows:

1. GI Chain link Rhombus shape approx. (2.5\*2.5) Sq. Cm.
2. Thickness of GI Chain link - 14 to 10 Gauge (i.e. 2.0 mm. to 3.0 mm. thick), as per availability.
3. GI Roll size - as per market availability.
4. Fencing height – preferably 4'-5' minimum (approx..) from the Existing Ground Level. Ground bed to be freed – 2" or 50.0 mm.
5. GI Chain Make - As per best availability in the local market.
6. Length of GI chain link fencing - as per practical site requirement. Total portion of damaged / unavailable existing fencing – need to be replaced / installed with new GI Chain link fencing.
7. Specification of materials as per the given standards needs be get certified from the officials before using.

प्रधान कार्यालय: पटसन भवन, तीसरी और चौथी मंजिल, ब्लॉक-सीएफ, एक्शन एरिया - 1, न्यू टाउन, कोलकाता - 700156


Head Office: Patsan Bhavan, 3rd & 4th Floor, Block-CF, Action Area – 1, New Town,

ई-मेल / E-mail: [jci@jciemail.in](mailto:jci@jciemail.in) | वेबसाइट / Website: [www.jutecorp.in](http://www.jutecorp.in)





भारतीय पटसन निगम लिमिटेड  
The Jute Corporation of India Limited  
(A Government of India Enterprise)



सी.आई.एन./ C.I.N.: U17232WB1971GOI027958

क्षेत्रीय कार्यालय: गौरीपुर / Regional Office: Gauripur

Super Market, Ward No1, Gauripur, Dhubri (Assam) – 783331

- (D) Seen MS Angle section, as the existing vertical post.
- (E) Some Vertical posts are seen in bent / leaning condition w.r.t. the Ground. Those need to be straightened & to be kept aligned properly.
- (F) If seen that some MS vertical posts are missing from the Fencing line or completely damaged, new MS Vertical post need to be installed on that portion. The new Vertical Post should have Angle section of  $< (100 * 100 * 8)$  mm. & it's Height to be matched with the Post(s) of both the sides of the new Angle.
- (G) Make of the Angle - TATA / SAIL / JINDAL.
- (H) All the vertical posts need to be jammed properly with Cement concrete (1:1.5:3 ratio), up to 150.0 mm. deep from the Gr. Level., before pulling GI chain link fencing. The nett excavation area shall be – (8" \* 8").
- (I) All the MS vertical posts, need to be painted properly with 01 coat of oil bound primer (metallic primer) & 02 coats of syn. enamel paint, after proper, rubbing, cleaning, smoothening of the surfaces etc. Make – ASIAN / BERGER / ICI / NEROLAC.
- (J) Any kind of small repairing, as required of the MS Angle vertical post, need to be done.
- (K) Pulling of GI chain link, to be done properly.
- (L) Fixing of GI chain link with MS post, to be done with GI nut, bolt & washer (with necessary shape, size).
- ☒ **Payment.** There will be no part/advance payment. Payment will be done on completion of work and after thorough inspection by office representative.
- ☒ **Mode of payment:** By online payment mode such as NEFT/RTGS etc. and within two weeks of completion of work.
- ☒ **Completion of work:** Work must be completed within 07 (Seven) days from the date of issuance of work order.
- ☒ **Liquidate Damage Clause:** For Delay beyond scheduled Completion Time, 1% of the Order Value, Per Week of Delay, Subject to maximum 10% of the Order Value.
- ☒ **Security Deposit:** 5% of Total contract value will be deducted from the final bill which will be released after the expiry of "Defect Liability Period" i.e. One Year from the date of completion of work.

प्रधान कार्यालय: पटसन भवन, तीसरी और चौथी मंजिल, ब्लॉक-सीएफ, एक्शन एरिया - 1, न्यू टाउन, कोलकाता - 700156


Head Office: Patsan Bhavan, 3rd & 4th Floor, Block-CF, Action Area – 1, New Town,

ई-मेल / E-mail: [jci@jcimail.in](mailto:jci@jcimail.in) | वेबसाइट / Website: [www.jutecorp.in](http://www.jutecorp.in)





भारतीय पटसन निगम लिमिटेड  
**The Jute Corporation of India Limited**  
(A Government of India Enterprise)



सी.आई.एन./ C.I.N.: U17232WB1971GOI027958

क्षेत्रीय कार्यालय: गौरीपुर / Regional Office: Gauripur

Super Market, Ward No1, Gauripur, Dhubri (Assam) – 783331

- ☒ **Acceptance of Tender.** The Office reserves the right to accept or reject any or all tenders without assigning any reasons whatsoever.
- ☒ **Submission of Quotations.** All interested person can see the actual scope of work by visiting the site and submit the quote by 22-04-2024. No further request for enhancement of rate of contract will be entertained. Quotations will be opened on 23-04-2024.

*S. Swarna Das*  
21.04.2024  
Regional Manager-IC  
Gauripur RLD

*Distribution:*

1. Notice board – Gauripur RLD